DP3 Hot Semi-sub Available for Private Sale

General Specifications

| GENERAL (U.S) | |
|----------------------------|---|
| Built | 2008 DSME |
| Design | GVA 7500 |
| Flag / Class / Notations | TBD / DNV / 1A1, DP3 |
| Dimensions | 386.8 ft Long / 317.3 ft Wide |
| Drafts | 75 ft Drilling / 32.6 ft Transit |
| Displacements | 60,757 st Drilling, 41,876 st Transit |
| Variable Load | 7,714 st Drilling / 6,888 st Transit |
| Accommodation | 180 Persons |
| Helideck | Sikorsky S61N & S92 |
| Max. Water Depth | 10,000 ft Designed / 10,000 ft Outfitted |
| Max. Drilling Depth | 35,000 ft |
| STATION KEEPING | |
| Dynamic Positioning | Dynpos Autro, Posmoor ATA, DP Class 3 |
| Thrusters | 8 x Rolls Royce 4,694 HP Azimuthing |
| Transit Speed | Up to 6 Knots |
| Mooring Lines | 8 x 5,577 ft 3.3" Chain |
| Mooring Winches | 4 x Double Pusnes 603 HP |
| STORAGE CAPACITIES | |
| Fuel | 21,309 bbl |
| Drill Water | 16,416 bbl |
| Potable Water | 3,283 bbl |
| Active Liquid Mud | 5,202 bbl |
| Reserve Liquid Mud | 11,598 bbl |
| Bulk Bentonite / Barite | 21,895 ft3 |
| Bulk Cement | 9,888 ft3 |
| Sack Storage (50 LB Sacks) | 7,500 Sacks |

| DRILLING PACKAGE | |
|--------------------|--|
| Derrick | AKMH 203 ft Tall with 46 ft x 52 ft Base Gross 2,000,000 lbs |
| Top Drive | MH DDM 1000 Rated for 1,000 st Hoisting Capacity, 2 x 1,150 HP AC Motors, Max. Continuous Torque 94,800 ft-lbs at 125 RPM |
| Drawworks | Wirth GH 4500 w/ 2" Drill Line Max. Line Pull 14 Lines of 2,284,000 lbs |
| Rotary Table | Wirth RTSS 60 1/2" |
| Compensator | MH Crown Mounted Rated for 1,000,000 lbs Compensated, 2,000,000 lbs Static |
| Tubular Handling | MH Hi-Pro Automated Racking System |
| Offline Capability | Offline Stand Building Arm / SBHRN |
| Mud Pumps | 4 x Wirth TPK 7-1/2" x 14" 2,200 HP |
| HP Mud System | Rated for 7,500 psi |
| Shale Shakers | 6 x Swaco BEM 650 |
| SUBSEA EQUIPMENT | |
| ВОР | 1 x Cameron 18 3/4" 5 RAM 15,000 psi |
| Annular | 2 x Cameron DL 18 3/4" 10,000 psi |
| Diverter | Hydril 59-1/2" |
| Riser | Cameron LK 75 ft Length 21" OD, 4" ID Boost Line |
| Tensioners | 6 x MH DATs Max. Total Tension Applied at Ring 1,800 st, 50 ft Stroke |
| Wellhead Connector | VETCO SHD-H4 |

DP3 Hot Semi-sub Available for Private Sale

General Specifications

| CRANES | |
|---------------------|--|
| Pedestal Cranes | 2 x Seatrax Rated for 110 st at 82 ft Radius |
| Pipe Handling Crane | 1 x AKMH Rated for 16 st at 49-82 ft Radius |
| X-Mas Tree Handling | 4 x 83 st SWL Skids for Storage and Stack up on Cellar Deck on X-mas Tree Skid of 220 st SWL |
| POWER | |
| Main Engines | 8 x Wartsila 6,312 HP at 720 RPM |
| Main generators | 8 x ABB 6,312 HP |
| Total power | Main Generators Classified as Emergency Generators |
| OTHER INFORMATION | |
| Harsh Environment | |